

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu
 Detail Estimate Sheet

Project:-नाइलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन
 Location:- Shankharapur Municipality- 1

F.Y.:-2082/083
 Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
A.	पानी ट्याङ्की मर्मत									
1	प्लेन सिमेन्ट कंक्रीट वा वज्र कंक्रीट भत्काई १० मी. पर हटाउने काम									
	-water tank	1.0	5.00	3.35	0.08	1.26				
						1.26	cum	3740.00	4702.07	
2	सिमेन्ट वा वज्रमा जोडेको गारो भत्काई त्यसबाट आएको सामग्री १० मी									
	-water tank	2.0	5.00	0.23	1.40	3.22				
		2.0	2.89	0.23	1.40	1.86				
		1.0	5.00	0.23	0.45	0.52				
						5.60	cum	1982.20	11101.03	
3	घाँस काट्ने त्यसको जरा फिक्ने, डिस्को फुटाउने र लेभल मिलाउने कार्य									
	-for levelling	1.0	13.99	7.62		106.64				
		1.0	2.29	9.16		20.93				
		1.0	2.67	8.79		23.44				
		1.0	3.96	8.31		32.91				
						183.91	sqm	23.00	4229.95	
4	साढो प्रकारको क्ले, नरम मुरम ढुंगा (३० से.मी.सम्म) मिसको माटोमा सवै किसिमको खन्ने काम									
		1.0	4.57	4.42	0.13	2.52				
						2.52	cum	770.43	1943.69	
5	सुख्खा ईटा च्याप्टो छाप्ने काम									
	-for flooring	1.0	4.57	4.42		20.18				
						20.18	sqm	166.50	3360.46	
6	जग भित्ता पर्खालमा सिमेन्ट कंक्रीट गर्ने काम (मि.सी.सी. १:२:४)									
	-for flooring	1.0	4.57	4.42	0.08	1.51				
						1.51	cum	13351.10	20209.83	
	vat on cement								820.57	
	vat on sand								278.28	
	vat on aggregate								539.19	
7	आर.सी.सी. लागि १० मि.मि. फलामे ढण्डी काट्ने, मोड्ने ३० मीटर सम्म									
	-Along long length	29.0	8.76		0.62	156.73			4.22	
		28.0	8.50		0.62	146.94				
	-Along short length	28.0	8.91		0.62	153.96				
		27.0	8.65		0.62	144.23				
	-binder	12.0	17.07		0.40	80.91				
		12.0	16.05		0.40	76.10				
	-Slab	56.0	4.42		0.40	97.77				
		58.0	4.27		0.40	97.77				
	-deduction for opening	-10.0	0.61		0.40	-2.41				
		-10.0	0.61		0.40	-2.41				
	-for fillet	50.0	1.34		0.40	26.53				
		48.0	1.34		0.40	25.47				
	-binder	1.0	14.53		0.40	5.74				

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu

Detail Estimate Sheet

Project:-नाडलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन

F.Y.:-2082/083

Location:- Shankharapur Municipality- 1

Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
	-for kitchen setup at ward office	5.0	1.50		0.89	6.67				
		11.0	0.71		0.89	6.94				
						1020.95	kg	132.36	135133.2	
	vat on material								14095.27	
8	फलामको पाइप र प्लाइवुडबाट फर्मा बनाउने काम									
	-For shear wall	1.0	17.37		1.80	31.29				
		1.0	15.75		1.50	23.57				
	-for slab	1.0	4.01	3.86		15.49				
	-deduction for opening	-1.0	0.61	0.61		-0.37				
	-for kitchen setup at ward office	1.0	1.50	0.71		1.07				
						71.05	sqm	922.71	65555.23	
	vat on material								4325.04	
9	मेशिनको प्रयोग गरी सुपर स्ट्रक्चरमा सिमेन्ट कंक्रीट गर्ने काम (१:१.५:३)									
	-floor and slab	2.0	4.42	4.27	0.13	4.71				
	-shear wall	2.0	4.42	0.20	1.68	3.01				
		2.0	3.86	0.20	1.68	2.63				
	-fillet	1.0	3.71	0.30	0.30	0.34				
		1.0	3.56	0.30	0.30	0.33				
	-deduction for opening	-1.0	0.60	0.60	0.13	-0.05				
	-for kitchen setup at ward office	1.0	1.50	0.71	0.13	0.13				
						11.12	cum	13957.29	155159.6	
	vat on cement								7532.84	
	vat on sand								1951.86	
	vat on aggregate								4095.08	
	vat on diesel								567.84	
	vat on petrol								20.45	
10	१२.५ मी.मी. सिमेन्ट बालुवा (१:४) प्लास्टर									
	-At shear wall	2.0	4.01		1.37	11.01				
		2.0	3.86		1.37	10.59				
	-at fillet	1.0	14.53		0.43	6.26				
	-for kitchen	3.0	0.71		0.80	1.70				
						29.56	sqm	415.50	12283.95	
	vat on cement								269.44	
	vat on sand								178.32	
11	सिमेन्ट कंक्रीट फ्लोरिङ (१:२:४) (३८ मी.मी.)									
	-at water tank	1.0	3.40	3.25		11.06				
	-at roof of ward office	1.0	4.14	5.11		21.13				
	-at cantilever	1.0	23.19	0.45		10.44				
		1.0	6.40	0.90		5.76				
		1.0	15.24	0.60		9.14				
		1.0	10.34	0.60		6.20				
						63.74	sqm	689.98	43979.99	
	vat on cement								1403.73	
	vat on sand								473.99	
	vat on aggregate								1000.66	

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu
 Detail Estimate Sheet

Project:-नाइलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन
 Location:- Shankharapur Municipality- 1

F.Y.:-2082/083
 Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
12	३ मी.मी. मोटाई मसीनो सिमेन्ट चोदने काम									
	-At shear wall	2.0	4.01		1.37	11.01				
		2.0	3.86		1.37	10.59				
	-for fillet	1.0	14.53		0.43	6.26				
	-at floor	1.0	3.40	3.25		11.06				
	-at roof of ward office	1.0	4.14	5.11		21.13				
	-at cantilever	1.0	23.19	0.45		10.44				
		1.0	6.40	0.90		5.76				
		1.0	15.24	0.60		9.14				
		1.0	10.34	0.60		6.20				
						91.60	sqm	287.32	26318.76	
	vat on cement								825.52	
13	square frame medium duty 24"X24	1.0				1.00	no.	4659.00	4659.00	
	vat for material								605.67	
14	(१:२ भागमा बाटर घुफ कम्पाउण्ड मिसाई डेम्प प्रुफिङ्ग गन									
	-as of item no. 11	1.0	91.60			91.60				
						91.60	sqm	452.86	41482.37	
	vat on cement								2094.85	
	vat on sand								681.17	
	vat on water-proofing compound								614.10	
15	भुईतल्लामा चिमनी भद्दाको ईटाको गारो सिमेन्ट मसला (१:४) मा									
	-for kitchen	3.0	0.71	0.10	0.80	0.17				
						0.17	cum	15170.83	2585.65	
	vat on brick								187.92	
	vat on cement								28.87	
	vat on sand								21.03	
	vat on water								0.81	
16	पोरसिलिन ग्लेज्ड टाईल(Ordinary floor and Wall Tile-as per approved standard of manufactured country) १:४ सिमेन्ट बालुवामा छान्ने काम ।									
	-for kitchen	1.0	3.23	4.06		13.12				
	-deduction for kitchen part	-1.0	1.52	0.71		-1.08				
	-at wall	1.0	1.52	0.76		1.16				
						13.20	sqm	2988.15	39448.83	
	vat on porcelain glazed tile								1150.93	
	vat on cement								125.24	
	vat on sand								88.43	
	vat on white cement								17.17	
17	१६ मी.मी.ग्रेनाईट, सिमेन्ट मसलामा छापी चोदने र पालिश समेत गर्न									
	-for kitchen	1.0	1.52	0.71		1.08				
						1.08	sqm	7012.25	7588.76	
	vat on 16mm granite								609.46	
	vat on cement								23.83	
	vat on sand								8.73	

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu

Detail Estimate Sheet

Project:-नाडलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन

F.Y.:-2082/083

Location:- Shankharapur Municipality- 1

Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
	vat on अक्जालिक एसिड								0.65	
	vat on मैन पालिश								0.61	
	vat on तारपेन्टाइन								1.67	
	vat on कार्बोरण्डम ढुंगा								1.69	
18	मालसामान उपलब्ध गरी ५० मी.मी. मोटो हेभी ड्यूटी इन्टरलकिंग कंक्रीटब्लक ५० मी.मी.मोटाइको क्रसर डस्ट माथी राखी बिछ्याउने काम पुरा ।									
	-for ward compound area	1.0	13.99	7.62		106.64				
		1.0	2.29	9.16		20.93				
		1.0	2.67	8.79		23.44				
		1.0	3.96	8.31		32.91				
	-deduction	-25.0	0.76	0.06		-3.80				
						180.11	sqm	1832.98	330139.92	
	vat on interlock block								8367.96	
	vat on ढुंगाको घूलो (एरियाट्र ५ से.मी.)								84.13	
	vat on ढुंगाको घूलो								2171.90	
19	सुब्बा ईटा ठाडो छाप्ने काम									
	-for rounding around plants	50.0	0.76	0.06		7.60				
						7.60	sqm	1834.54	13942.27	
	vat on materials								1360.01	
20	एक कोट प्राईमर सहित दुई कोट वेदरकोट पेन्ट गर्ने काम									
	-ward compound	2.0	3.42		1.43	9.77				
		2.0	0.96		2.20	4.22				
		2.0	4.00		1.39	11.12				
		2.0	0.96		2.20	4.22				
		2.0	3.91		1.30	10.17				
		2.0	0.96		2.31	4.44				
		2.0	3.96		1.37	10.85				
		2.0	0.96		2.29	4.40				
		2.0	3.88		1.27	9.80				
		2.0	0.96		2.19	4.20				
		2.0	3.69		1.28	9.45				
		2.0	0.96		2.19	4.20				
		2.0	4.17		1.12	9.34				
		2.0	0.68		2.26	3.07				
		2.0	0.68		2.15	2.92				
		2.0	2.50		1.16	5.80				
		2.0	0.96		2.18	4.19				
		2.0	3.94		1.20	9.46				
		2.0	0.96		2.15	4.13				
		2.0	4.00		1.15	9.20				
		2.0	0.96		2.08	3.99				
		2.0	3.97		1.25	9.93				
		2.0	0.96		2.25	4.32				
		2.0	4.00		1.23	9.84				
		2.0	0.96		2.25	4.32				
		2.0	4.06		1.32	10.72				
		2.0	0.96		2.18	4.19				
		2.0	3.92		1.32	10.35				

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu

Detail Estimate Sheet

Project:-नाङ्गलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन

F.Y.:-2082/083

Location:- Shankharapur Municipality- 1

Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
		2.0	0.96		2.28	4.38				
		2.0	3.62		1.32	9.56				
		2.0	0.96		2.20	4.22				
		-32.0	0.23		1.35	-9.94				
	-at roof parapet of ward office	1.0	19.71		0.52	10.25				
		1.0	18.49		0.52	9.61				
	- at toilet renovated	2.0	0.76		2.13	3.25				
						223.94	sqm	253.80	56835.92	
	vat on aster								670.74	
	vat on weather coat								3036.98	
21	भित्ता एवम् सिलिङ्गमा २ मि.मि. प्लेन ह्वाइट पुष्टी प्लाष्टर गर्ने कार्य									
	-at ward office room 1	1.0	15.44		2.67	41.18				
	-ceiling	1.0	3.76	3.96		14.89				
	-room 2	1.0	18.70		2.67	49.86				
	-ceiling	1.0	5.26	4.09		21.50				
	-room 3	1.0	14.78		2.67	39.43				
	-ceiling	1.0	3.30	4.09		13.50				
	-deduction for door	-3.0	1.07		2.13	-6.83				
	-deduction for window	-6.0	1.83		1.22	-13.38				
		-1.0	1.22		1.22	-1.49				
						158.67	sqm	300.03	47606.18	
	vat on white patty								1382.69	
22	एक कोट वाटर प्रुफ सिमेन्ट कोट लगाउने काम									
	-room 2	1.0	5.26		2.67	14.02				
	-room 3	1.0	6.60		2.67	17.61				
	-deduction for door	-1.0	1.07		2.13	-2.28				
	-deduction for window	-2.0	1.83		1.22	-4.46				
		-1.0	1.22		1.22	-1.49				
						23.41	sqm	60.30	1411.66	
	vat on cement paint								63.00	
23	प्राईमर बाहेक दुई कोट तयारी बासेबल डिस्टेम्पर लगाउने काम ।									
	-at Ground Floor									
	-at ward sadasya room	1.0	25.40		2.67	67.74				
	-at passage, toilet and staircase area	1.0	25.20		2.67	67.19				
	-deduction for door	-1.0	1.20		2.44	-2.93				
		-1.0	1.07		2.10	-2.24				
		-1.0	0.75		1.80	-1.35				
	-deduction for window	-1.0	0.90		1.80	-1.62				
		-6.0	1.80		1.20	-12.96				
		-1.0	1.20		1.20	-1.44				
	-at first floor									
	-at passage and staircase area	1.0	17.42		2.67	46.47				
	-deduction for door	-4.0	1.07		2.10	-8.96				
		-1.0	0.75		1.80	-1.35				
	-deduction for window	-1.0	0.90		1.80	-1.62				
	-at top floor									
	-at passage and staircase area	1.0	14.63		2.67	39.02				
	-at kitchen	1.0	10.67		2.64	28.18				

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu

Detail Estimate Sheet

Project:-नाइलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन

F.Y.:-2082/083

Location:- Shankharapur Municipality- 1

Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
		1.0	4.01	3.33		13.36				
	-deduction for kitchen rack area	-1.0	1.50		0.90	-1.35				
	-deduction for door	-1.0	1.07		1.80	-1.92				
	-deduction for window	-1.0	1.80		1.37	-2.47				
						221.75	sqm	125.50	27829.26	
	vat on washable distemper								1065.45	
24	अस्तर बाहेक दुई कोट बेदर कोट गर्ने काम									
	-at Ground Floor									
	-at outer face	1.0	35.61		2.84	101.26				
	-deduction for door	-1.0	1.20		2.44	-2.93				
	-deduction for window	-1.0	0.90		1.80	-1.62				
		-6.0	1.80		1.20	-12.96				
		-1.0	1.20		1.20	-1.44				
		-1.0	0.90		1.20	-1.08				
	-at first floor									
	-at outer face	1.0	35.61		2.84	101.26				
	-deduction for door	-1.0	1.07		2.10	-2.24				
	-deduction for window	-1.0	0.90		1.80	-1.62				
		-6.0	1.80		1.20	-12.96				
		-1.0	1.20		1.20	-1.44				
		-1.0	0.90		1.20	-1.08				
	-at top floor									
	-at outer face of staircase area	1.0	8.13		2.84	23.11				
						186.27	sqm	192.85	35921.32	
	vat on washable distemper								2526.06	
25	20mm GI Pipe threaded -Medium class									
	- for kitchen	1.0	0.90			0.90				
	-for outside dhara	1.0	1.50			1.50				
	-for water tank inlet and overflow	2.0	0.90			1.80				
						4.20	rm	248.00	1041.60	
	-13% VAT on materials								135.41	
26	PPR pipe (PN-16) 20mm OD 2.80mm thick 0.148kg/m									
	-for kitchen	1.0	9.00			9.00				
						9.00	rm	75.00	675.00	
	-13% VAT on materials								87.75	
27	Porcelain clay white glaze wash basin large size regular complete set									
	-for kitchen	1.0				1.00				
						1.00	set	1070.00	1070.00	
	-13% VAT on materials								139.10	
28	Brass tap-1'2" ordinary									
	-for kitchen and outside dhara	2.0				2.00				
						2.00	set	750.00	1500.00	
	-13% VAT on materials								195.00	

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu

Detail Estimate Sheet

Project:-नाइलेभारे स्वास्थ्य चौकी पानी ट्याङ्की मर्मत तथा वडा कार्यालय कम्पाउण्ड रंगरोगन

F.Y.:-2082/083

Location:- Shankharapur Municipality- 1

Date: 2082/04/01

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
29	Provisional sum for unforeseen works at kitchen and water tank	1.0				1.00	PS	25000.00	25000.00	
30	Information Board and photographs	1.0				1.00	no.	500.00	500.00	
									1189146.9	

Description	Amount	Percent
Total Estimated	1,189,146.87	
Budget Allocated	1,050,000.00	100.0
Municipal Payment	997,500.00	83.88
User Contribution	191,646.87	18.25
Maintenance 2%	21,000.00	2.00
Contingencies 3%	31,500.00	3.00

Prepared By:

Checked By:

Approved By: