

Government of Nepal
Shankharapur Municipality Office
 Bagmati Province
 Sankhu, Kathmandu
Detail Estimated Sheet

Project:-Nanglebhare Police Chauki
 Location:- Shankharapur Municipality 9

F.Y.: 2082/2083
 Date:

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
1	Earthwork Excavation in Cutting., Roadway Excavation in all types of Soil by Mechanical Means ., Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.									
	-for brick wall	1	39.40	0.30	0.75	8.87				
		16	0.35	0.35	0.75	1.47				
	-for stone masonry	1	45.00	0.75	1.00	33.75				
	Sub-total					44.09	m3	62.95	2775.15	
	-13% VAT for materials								296.30	
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.									
	-for stone masonry	1	45.00	0.75	0.15	5.06				
	Sub-total					5.06	m3	4585.53	23214.25	
	-13% VAT for materials								2033.95	
3	सुख्खा ईटा च्याप्तो छाप्ने काम									
	-for brick wall	1	39.40	0.23		9.06				
		16	0.35	0.35		1.96				
	Sub-total					11.02	m3	1017.47	11214.55	
	-13% VAT for materials								1234.72	
4	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications, PCC Grade M 15									
	-for brick wall	1	39.40	0.23	0.08	0.68				
		2	39.40	0.23	0.08	1.36				
		16	0.35	0.35	0.05	0.10				
		16	0.35	0.35	0.08	0.15				
	-for stone masonry	1	45.00	0.50	0.08	1.69				
		1	45.00	0.45	0.05	1.01				
	Sub-total					4.98	m3	10964.46	54646.32	
	-13% VAT for materials								5432.80	
5	भुईतल्लामा चिम्नी भट्टाको ईटाको गारो सिमेन्ट मसला (१:६) मा									
	-for brick wall	1	39.40	0.23	1.35	12.23				
	Sub-total					12.23	m3	14491.84	177288.82	
	-13% VAT for materials								16499.79	

Prepared By:

Checked By:

Approved By:

Government of Nepal

Shankharapur Municipality Office

Bagmati Province

Sankhu, Kathmandu

Detail Estimated Sheet

Project:-Nanglebhare Police Chauki

F.Y.: 2082/2083

Location:- Shankharapur Municipality 9

Date:

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Rate	Amount	Remark
6	१२.५ मी.मी. सिमेन्ट बालुवा (१:४) प्लाष्टर									
	-for brick wall	2.0	45.00		0.90	81.00				
	sub-total					81.00	sqm	415.50	33655.50	
	-VAT 13% for materials								1226.79	
7	एक कोट प्राईमर सहित दुई कोट वेदरकोट पेन्ट गर्ने काम									
	-for brick wall	2.0	45.00		0.90	81.00				
	sub-total					81.00	sqm	253.80	20557.80	
	-VAT 13% for materials								1341.10	
8	Random Rubble Masonry, Providing and laying of Stone Masonry Work in Cement Mortar 1:6 in Foundation complete as per Drawing and Technical Specifications.									
	-for stone masonry	1	45.00	0.48	1.00	21.38				
	Sub-total					21.38	m3	9878.43	211151.44	
	-13% VAT for materials								15331.53	
9	Information board (सुचना पाटि)	1.0				1.00	no.	500.00	500.00	
	Total								578400.81	

Total Estimated	578400.81	100.00
Budget allocated	500000.00	
Municipal payment	475000.00	82.12
Police sector contribution	103400.81	17.88
Contingencies	15000.00	3.00
Maintanince	10000.00	2.00