

Government of Nepal
Shankharapur Municipality
Shankhu, Kathmandu
Detail Estimate Sheet

Project:-पंचपाले क्षेत्रमा सिँचाई ट्याङ्की

-2083/084

Location:- Shankharapur Municipality- 1

Date: 2082/06/14

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Remark
A.	पानी ट्याङ्की मर्मत							
1	हाइड्रोलिक एक्साभेटर प्रयोग गरी माटो खन्ने काम							
		1.0	8.07	4.57	1.19	43.84		
						43.84	cum	
2	जगको खाडलमा ढुंगा भर्ने र लेभल गर्ने काममा							
	-for flooring	1.0	8.07	4.57	0.15	5.53		
						5.53	sqm	
3	जग भित्ता पर्खालमा सिमेन्ट कंक्रीट गर्ने काम (पि.सी.सी. १:२:४)							
	-for flooring	1.0	8.07	4.57	0.08	2.77		
						2.77	cum	
4	आर.सी.सी. लागि १० मि.मि. फलामे डण्डी काट्ने, मोड्ने ३० मीटर सम्म							
	-Along long length	47.0	7.85		0.62	227.63		
		45.0	7.59		0.62	210.88		
	-Along short length	25.0	11.35		0.62	175.17		
		24.0	11.10		0.62	164.40		
	-binder	12.0	24.38		0.40	115.59		
		12.0	23.37		0.40	110.78		
	-for fillet	92.0	1.34		0.40	48.81		
		46.0	1.34		0.40	24.41		
	-binder	1.0	21.84		0.40	8.63		
	-for column	6.0	2.58		1.58	24.43		
	-stirrups	12.0	1.30		0.40	6.16		
		12.0	1.02		0.40	4.84		
						1121.72	kg	
5	फलामको पाइप र प्लाइवुर्डबाट फर्मा बनाउने काम							
	-For shear wall	1.0	24.69		1.68	41.38		
		1.0	23.06		1.37	31.63		
	-for column	6.0	0.36	0.36	1.68	1.27		
						74.29	sqm	
6	मेशिनको प्रयोग गरी सुपर स्ट्रक्चरमा सिमेन्ट कंक्रीट गर्ने काम (१:१.५:३)							
	-floor and slab	1.0	7.92	4.42	0.13	4.38		
	-shear wall	2.0	7.21	0.20	1.68	4.91		
		2.0	2.95	0.20	1.68	2.01		
	-fillet	1.0	6.15	0.30	0.30	0.57		
		1.0	2.64	0.30	0.30	0.25		
	-for column	6.0	0.36	0.36	0.30	0.23		
						12.11	cum	
7	१२.५ सी.सी. सिमेन्ट बालुवा (१:४) प्लाष्टर							
	-At shear wall	2.0	7.52		1.37	20.62		

Government of Nepal
Shankharapur Municipality

Shankhu, Kathmandu
 Detail Estimate Sheet

Project:-पंचपाले क्षेत्रमा सिँचाई ट्याङ्की

-2083/084

Location:- Shankharapur Municipality- 1

ate: 2082/06/14

S.N.	Description of work	No.	Length	Breadth	Height	Quantity	Unit	Remark
		2.0	4.01		1.37	11.01		
	-at fillet	1.0	17.58		0.43	7.58		
						39.21	sqm	
8	सिमेन्ट कंक्रीट फ्लोरिङ (१:२:४) (३८ मी.मी.)							
	-at water tank	1.0	6.91	3.40		23.51		
						23.51	sqm	
9	३ मी.मी. मोटाई मसीनो सिमेन्ट घोटने काम							
	-At shear wall	2.0	7.52		1.37	20.62		
		2.0	4.01		1.37	11.01		
	-for fillet	1.0	17.58		0.43	7.58		
	-at floor	1.0	6.91	3.40		23.51		
						62.72	sqm	
10	square frame medium duty 24"X24	1.0				1.00	no.	
11	(१:२ भागमा वाटर पुफ कम्पाउण्ड भिसाई डेम्प पुफिङ गन							
	-as of item no. 11	1.0	62.72			62.72		
						62.72	sqm	
12	Provisional sum for unforeseen works of water tank	1.0				1.00	PS	
13	Information Board and photographs	1.0				1.00	no.	

Description	Amount	Percent
Total Estimated	559,448.18	
Budget Allocated	500,000.00	100.0
Municipal Payment	475,000.00	84.91
User Contribution	84,448.18	16.89
Maintenance 2%	10,000.00	2.00
Contingencies 3%	15,000.00	3.00