

नेपाल सरकार
संस्कृति, पर्यटन तथा नागरिक उड्डयन मन्त्रालय

पुरातत्त्व विभाग

दर विश्लेषण

(Rate Analysis)

२०८२/ ०८३

TABLE OF CONTENTS

क्र.स.	कामको विवरण	आईटम नं.
(क)	भत्काउने सम्बन्धी कार्य	1 to 7
(ख)	जग खन्ने सम्बन्धी कार्य	8 to 9
(ग)	चुना कंक्रीट सम्बन्धी कार्य	10 to 11
(घ)	भुईँ सम्बन्धी कार्य	12 to 21
(ङ)	ईँट्टा सम्बन्धी कार्य	22 to 60
(च)	ढुंगा सम्बन्धी कार्य	61 to 80
(छ)	प्लास्टर सम्बन्धी कार्य	81 to 84
(ज)	टिपकारी सम्बन्धी कार्य	85 to 88
(झ)	रंगरोगन सम्बन्धी कार्य	89
(ञ)	काठ सम्बन्धी कार्य	90 to 117
(ट)	छाना सम्बन्धी कार्य	118 to 142
(ठ)	खट वाँधने सम्बन्धी कार्य	143 to 147
(ड)	धातु सम्बन्धी कार्य	148 to 153
(ढ)	कार्निस सम्बन्धी कार्य	154



Government of Nepal
Ministry of Culture, Tourism & Civil Aviation
Department of Archaeology
Item Rates

Project:- Inside Kathmandu Valley

Fiscal Year:- 2082/83

Item No.	Item name	Unit	Rate per unit (Rs.)	Unit	Rate per Unit (Rs.)
(क) भत्काउने सम्बन्धी कार्य					
Item:- 1	Dismantling Chimney Brick work in mud mortar and throwing 10 metre away.	m3	1139.77	ft3	32.27
Item:- 2	Dismantling Chimney Brick work in cement mortar and throwing 10 metre away.	m3	2279.53	ft3	64.55
Item:- 3	Dismantling R.C.C. or R.B.C work and throwing 10 metre away.	m3	11827.75	ft3	334.92
Item:- 4	Dismantling Plain cement or lime concrete and throwing 10 metre away.	m3	4301.00	ft3	121.79
Item:- 5	Dismantling Cement or Lime Plaster and throwing 10 metre away.	m2	116.13	ft2	10.79
Item:- 6	Dismantling Jhingati roofing and throwing 10 metre away.	m2	171.87	ft2	15.97
Item:- 7	Dismantling Tile roofing and throwing 10 metre away.	m2	164.42	ft2	15.28
(ख) जग खन्ने सम्बन्धी कार्य					
Item:- 8	Earth work in Excavation---soft and silty clay	m3	775.26	ft3	21.95
Item:- 9	Earth work in Excavation---Hard clay with soft stone	m3	886.01	ft3	25.09
(ग) चुना कंक्रीट सम्बन्धी कार्य					
Item:- 10	Lime Concrete in Foundation and wall in (1:2:4) lime, sand and brick ballast.	m3	16496.00	ft3	467.11
Item:- 11	Lime Concrete in Foundation and wall in (1:2:4) lime, sand and aggregate.	m3	16321.03	ft3	462.16
(घ) भुई सम्बन्धी कार्य					
Item:- 12	Chimney Brick on flat Soling	m2	1169.89	ft2	108.73
Item:- 13	Chimney Brick on flat Soling using existing brick	m2	438.63	ft2	40.76
Item:- 14	Chimney Brick on edge Soling	m2	2057.97	ft2	191.26
Item:- 15	Lachhi Brick on edge Soling (size 190x104x60mm)	m2	3846.79	ft2	357.51

Prepared By:-

Checked By:-

Approved By:-

Item:- 16	Brick soling on edge in lime, surkhi and sand (1:1:2) with (1:1) lime surkhi pointing	m2	2504.56	ft2	232.77
Item:- 17	Old Brick soling on edge in lime, surkhi and sand (1:1:2) with (1:1) lime surkhi pointing	m2	1255.66	ft2	116.70
Item:- 18	Telia Brick (Machine made) 6"x6" in (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	m2	3529.87	ft2	328.05
Item:- 19	Telia Brick in Machine made 8"x8" (1:1:1) lime, surkhi, sand mortar with (1:1) lime surkhi pointing	m2	3863.83	ft2	359.09
Item:- 20	25 to 37.5 mm thick Flag Stone laying in (1:1:2) lime, surkhi, sand mortar.	m2	2351.26	ft2	218.52
Item:- 21	50 mm thick Flag Stone laying in (1:1:2) lime, surkhi, sand mortar.	m2	2594.76	ft2	241.15

(इ) ईट्टा सम्बन्धी कार्य


Item:- 22	Chimney Brick work in mud mortar for ground floor	m3	13378.48	ft3	378.83
Item:- 23	Chimney Brick work in mud mortar for above ground floor	m3	13916.10	ft3	394.06
Item:- 24	Chimney Brick work in mud mortar for ground floor (using existing bricks)	m3	3628.32	ft3	102.74
Item:- 25	Chimney Brick work in mud mortar for above ground floor (using existing bricks)	m3	4165.94	ft3	117.97
Item:- 26	Chimney Brick work in (1:1:2) lime, surkhi, sand mortar for ground floor	m3	18270.11	ft3	517.35
Item:- 27	Chimney Brick work in (1:1:2) lime, surkhi, sand mortar for above ground floor	m3	18807.73	ft3	532.57
Item:- 28	Traditional Brick (Small Dachi Appa) size 210x55x97 mm work in (1:1:2) lime, surkhi, sand mortar	m2	6183.61	ft2	574.68
Item:- 29	Traditional Brick (Small Dachi Appa) size 210x55x97 mm work in (1:4) cement sand mortar	m2	5864.18	ft2	545.00
Item:- 30	Traditional Brick (Dachi Appa-large size) size 230x55x100 mm work in (1:1:2) lime, surkhi, sand mortar	m2	0.00	ft2	0.00
Item:- 31	Traditional Brick (small Dachi Appa) work in yellow mud mortar	m2	5545.94	ft2	515.42
Item:- 32	Traditional Brick (Small Dachi Appa) work using existing old bricks in yellow mud mortar	m2	2305.00	ft2	214.22
Item:- 33	Traditional Brick (Dachi Appa-large size) work using existing old bricks in (1:1:2) lime, surkhi	m2	2942.66	ft2	273.48
Item:- 34	Ma Appa (Traditional Local Brick--large) work in yellow mud mortar for ground floor	m3	0.00	ft3	0.00
Item:- 35	Ma Appa (Traditional Local Brick--small) size 210x120x50 mm work in yellow mud mortar for ground floor	m3	17167.27	ft3	486.12

Prepared By:-


Checked By:-

Approved By:-

Item - 36	Ma Appa (Traditional Local Brick--large) size 230x50x125mm work in yellow mud mortar for above ground floor	m3	0 00	ft3	0 00
Item - 37	Ma Appa (Traditional Local Brick--small) size 210x120x50 mm work in yellow mud mortar for above ground floor	m3	17704 89	ft3	501 34
Item - 38	Ma appa Brick(large) size 230x50x125mm work in (1:1:2) lime,surkhi, sand mortar for ground floor	m3	0 00	ft3	0 00
Item - 39	Ma appa Brick(large) size 230x50x125mm work in (1:1:2) lime,surkhi, sand mortar for above ground floor	m3	0 00	ft3	0 00
Item - 40	Ma appa Brick(small) size 210x120x50 mm work in (1:1:2) lime,surkhi, sand mortar for ground floor	m3	22194 02	ft3	628 46
Item - 41	Ma appa Brick(small) size 210x120x50 mm work in (1:1:2) lime,surkhi, sand mortar for above ground floor	m3	22731 65	ft3	643 68
Item - 42	Existing Ma appa Brick(large) work in (1:1:2) lime,surkhi, sand mortar for above ground floor	m3	9462 95	ft3	267 96
Item - 43	Existing Ma appa Brick(small) work in (1:1:2) lime,surkhi, sand mortar for ground floor	m3	8925 32	ft3	252 73
Item - 44	Traditional Kassimo Brick work in (1:1:2) lime,surkhi, sand mortar	m	386 10	ft	117 71
Item - 45	Traditional Nago Brick work in (1:1:2) lime,surkhi, sand mortar	m	467 06	ft	142 40
Item - 46	Traditional Jhallar Brick work in (1:1:2) lime,surkhi, sand mortar	m	472 14	ft	143 95
Item - 47	Traditional Kerafo Brick work in (1:1:2) lime,surkhi, sand mortar	m	478 10	ft	145 76
Item - 48	Traditional sikri Brick work in (1:1:2) lime,surkhi, sand mortar	m	386 10	ft	117 71
Item - 49	Traditional Sinkhwa 2" with astamangal or full butta Brick work in (1:1:2) lime,surkhi, sand mortar	m	595 29	ft	181 49
Item - 50	Traditional Sinkhwa 3" with astmangal or full butta Brick work in (1:1:2) lime,surkhi, sand mortar	m	960 71	ft	292 90
Item - 51	Traditional Sinkhwa 4" Brick with astmangal or full butta work in (1:1:2) lime,surkhi, sand mortar	m	1195 69	ft	364 54
Item - 52	Traditional Palefo Brick work in (1:1:2) lime,surkhi, sand mortar	m	489 14	ft	149 13
Item - 53	Traditional Ba fya Brick work in (1:1:2) lime,surkhi, sand mortar	m	950 93	ft	289 92
Item - 54	Traditional Fya Brick work in (1:1:2) lime,surkhi, sand mortar	m	467 06	ft	142 40
Item - 55	Traditional Nagabeli Brick work in (1:1:2) lime,surkhi, sand mortar	m	448 66	ft	136 79
Item - 56	Traditional Tinkune pali Brick work in (1:1:2) lime,surkhi, sand mortar	m	408 18	ft	124 45
Item - 57	Traditional Gol nagol Brick work in (1:1:2) lime,surkhi, sand mortar	m	386 10	ft	117 71

Prepared By: 

Checked By:-

Approved By:- 

Item - 58	Snake Carnesh Brick Work in (1:1:2) lime surkhi, sand mortar	m	483.85	ft	147.52
Item - 59	Mikha fushi Carnesh over wooden frame in 1:1:2 lime surkhi and sand	m	510.19	ft	155.55
Item - 60	Lhakayan works (taking two number in one set)	no	7094.55	no	7094.55

(च) ढुंगा सम्बन्धी कार्य

Item - 61	Stone work in foundation in lime surkhi sand 1:1:2 ratio	m3	16808.47	ft3	475.96
Item - 62	Stone work in foundation in lime stone dust 1:4 ratio	m3	14847.68	ft3	420.44
Item - 63	Stone work with existing stone in foundation in lime surkhi sand 1:1:2 ratio	m3	13547.30	ft3	383.61
Item - 64	Highly Dressed stone wall with chisel finishing in lime surkhi, sand (1:1:2) stone width not < 15 cm.	m3	51341.77	ft3	1453.82
Item - 65	Highly Dressed stone wall with chisel finishing in lime surkhi, sand (1:1:2) with old stone width not < 15 cm.	m3	15741.17	ft3	445.74
Item - 66	Highly Dressed stone wall with chisel finishing in cement sand (1:4)_ stone width not < 15cm	m3	48786.61	ft3	1381.47
Item - 67	Highly Dressed stone wall with chisel finishing in lime stone dust (1:3) stone width not < 15 cm.	m3	49215.10	ft3	1393.60
Item - 68	One side Dressed (Ashlar masonry) stone wall with chisel finishing in lime surkhi, sand (1:1:2)_ stone width not < 15 cm	m3	32487.72	ft3	919.94
Item - 69	One side Dressed (Ashlar masonry) stone wall with chisel finishing in cement, sand (1:4) width not < 15 cm	m3	31013.50	ft3	878.20
Item - 70	4" Peti Stone (10" X4") work in (1:1:1) lime, surkhi, sand mortar	r.m.	5003.76	r.ft	1525.54
Item - 71	5" Peti Stone work in (1:1:1) lime, surkhi, sand mortar size < 12"x10"x5"	r.m.	6243.28	r.ft	1903.44
Item - 72	5" Peti Stone work in (1:1:1) lime, surkhi, sand mortar using existing stone	r.m.	698.44	r.ft	212.94
Item - 73	5" Peti Stone work in cement : sand (1:4) size 10"x5" cement sand mortar	r.m.	6061.35	r.ft	1847.97
Item - 74	Corner Nhekan Stone work (23cm *23cm *35cm)	no	3143.07	no	3143.07
Item - 75	Middle Nhekan Stone work (23cm *23cm *35cm.)	no	1792.97	no	1792.97
Item - 76	4" Nagol Stone (10" X4") work in (1:1:1) lime, surkhi, sand mortar	r.m.	4211.64	r.ft	1284.04
Item - 77	5" Nagol Stone (10" X5") work in (1:1:1) lime, surkhi, sand mortar	r.m.	5649.19	r.ft	1722.31
Item - 78	Black saddle Base stone (12"x12"x10" size) for wooden column.	no	11848.37	no	11848.37
Item - 79	Stone highly carving works excluding stone	m2	100619.25	ft2	9351.23
Item - 80	Stone medium carving work excluding stone	m2	33758.25	ft2	3137.38

Prepared By

Checked By -

Approved By -

(छ) प्लास्टर सम्बन्धी कार्य

Item - 81	12.5 mm thick lime, surkhi and sand plaster in 1:1:2 ratio	m2	647.03	ft2	60.13
Item - 82	20 mm thick lime, surkhi and sand plaster in 1:1:2 ratio	m2	848.70	ft2	78.88
Item - 83	12.5 mm thick mud Liun plaster with surface cleaning, wetting curing and plastering all complete.	m2	482.16	ft2	44.81
Item - 84	25 mm thick Liun plaster with surface cleaning, wetting curing and plastering all complete.	m2	632.83	ft2	58.81

(ज) टिपकारी सम्बन्धी कार्य

Item - 85	Flush pointing in (1:1:2) lime, surkhi, sand on Brick wall.	m2	370.76	ft2	34.46
Item - 86	Flush pointing in (1:1:2) lime, surkhi, sand on dressed stone/Boulder stone wall.	m2	444.38	ft2	41.30
Item - 87	Flush Liun pointing in on Brick wall	m2	95.17	ft2	8.84
Item - 88	Traditional Flush siley pointing	m2	1518.53	ft2	141.13

(झ) रंगरोगन सम्बन्धी कार्य

Item - 89	Wood Preservative paint with Double boiled linseed oil , Dursban insecticide, with Tarpin (1:1:8)	m2	128.20	ft2	11.91
-----------	---	----	--------	-----	-------

(ञ) काठ सम्बन्धी कार्य

Item - 90	Sal Wood shoring work	m3	55903.95	ft3	1583.01
Item - 91	Sal Wood shoring using existing wood	m3	22591.75	ft3	639.72
Item - 92	Sal Timber work for beam,joist,column etc (up to 8'-0")	m3	286933.76	ft3	8124.98
Item - 93	Nepali Sal wood work for beam,joist,column etc (8'-0" to 12'-0")	m3	307061.19	ft3	8694.92
Item - 94	Sal Timber work for beam,joist,column etc (12'-0" above)	m3	322753.77	ft3	9139.28
Item - 95	Sal Timber work for chaukhat frame (up to 8'-0")	m3	367986.42	ft3	10420.12
Item - 96	1"thick Nepali Sal wood planking works with three side plainning not < 4" width	m2	6680.87	ft2	620.90
Item - 97	1.5" thick Eaves Board of Sal wood with three side plainning	m2	11219.97	ft2	1042.75
Item - 98	2"(5cm) sal wood plain shutter with Gand and khur.	m2	14465.22	ft2	1344.35

Prepared By -

Checked By -

Approved By -

Item - 99	Window carving (except lattice jali) including wood	m2	78833 71	ft2	7326 55
Item - 100	Window carving (except lattice jali) excluding wood	m2	51629 94	ft2	4798 32
Item - 101	Carved salwood Lattice (jali) of Carved Window highly carving including wood	m2	70473 67	ft2	6549 60
Item - 102	Carved salwood Lattice (jali) of Carved Window highly carving excluding wood	m2	58112 50	ft2	5400 79
Item - 103	Wooden Column highly carving works excluding wood	m2	55959 43	ft2	5200 69
Item - 104	Wooden Column medium carving work excluding wood	m2	40325 57	ft2	3747 73
Item - 105	Salwood Carved Mirap works including wood(between careved Post)	m2	70503 02	ft2	6552 33
Item - 106	Beam carving works above Column excluding wood	m2	44562 50	ft2	4141 50
Item - 107	Carnesh carving works excluding wood	m2	45010 98	ft2	4183 18
Item - 108	Carved Tudal(6"x4"x6") works including wood	no	58617 57	no	58617 57
Item - 109	Carved Kunsal(6'6"x5"x8") works including wood	no	47821 60	no	47821 60
Item - 110	Carved Three Bay Window(except jali) works including wood	m2	82039 09	ft2	7624 45
Item - 111	Carved Three Bay Window(except jali) works excluding wood	m2	49373 10	ft2	4588 58
Item - 112	Carved Door (except khapa) works excluding wood	m2	47303 91	ft2	4396 27
Item - 113	Carved Nas 3"thick works excluding wood	m	3714 50	ft	1132 47
Item - 114	Window carving (except lattice jali) including wood	m2	78833 71	ft2	7326 55
Item - 115	Carved salwood Lattice (jali) shutter of Carved door /window including wood	m2	37363 64	ft2	3472 46
Item - 116	Carved Tudal works excluding wood	m2	172060 47	ft2	15990 75
Item - 117	Carved Kunsal works excluding wood	m2	82288 50	ft2	7647 63

(ट) छाना सम्बन्धी कार्य

Item - 118	New Jhingati (8-3/4"x4") laying on roof with 3" clay	m2	5901 58	ft2	548 47
Item - 119	Old Jhingati (8-3/4"x4") laying on roof with 3" clay	m2	3354 98	ft2	311 80
Item - 120	Old Jhingati (8-3/4"x4") laying (using existing jhingati)on roof with 3" clay	m2	1276 13	ft2	118 60
Item - 121	Middle class Gongacha (Corner bird) fixing works	no	294 40	no	294 40
Item - 122	Jhingati Nailing works	r.m	109 04	r.ft	33 24
Item - 123	Dhuri Chang small (horizontal and vertical)works size 203x152x25 mm	r.m	2360 56	r.ft	719 68

Prepared By

Checked By -

Approved By -


Item - 124	Dhuri Chang (horizontal and vertical)___small sized using existing	r m	242 19	r ft	73 84
Item - 125	Dhuri Chang (horizontal and vertical)___large sized 254x203x25mm works	r m	6622 44	r ft	2019 04
Item - 126	Two layers of plastic felt laying on roofing with bitumen	m2	1145 35	ft2	106 45
Item - 127	Single layers of plastic felt laying on roofing with bitumen	m2	694 55	ft2	64 55
Item - 128	0 50 mm 24 gauge(medium) colour plain sheet roofing works	m2	1978 40	ft2	183 87
Item - 129	0 50 mm 24 gauge(medium) colour plain sheet ridge roofing works	r m	1195 30	r ft	364 42
Item - 130	20 gauge Brass plate making and fixing on roof	m2	15116 97	ft2	1404 92
Item - 131	22 gauge Copper plate making and fixing on roof	m2	14270 61	ft2	1326 26
Item - 132	26 gauge Copper plate making and fixing on roof (Indian)	m2	9391 98	ft2	872 86
Item - 133	22 gauge Brass plate making and fixing on roof	m2	12345 76	ft2	1147 38
Item - 134	26 gauge Brass plate making and fixing on roof	m2	8188 94	ft2	761 05
Item - 135	20/22 /26 gauge copper sheet gajur making and fixing on roof.	kg	4603 22	kg	4603 22
Item - 136	20/22 /26 gauge brass sheet gajur making and fixing on roof.	kg	4352 75	kg	4352 75
Item - 137	20/22 /26 gauge 6"/8" copper/brass sheet Eaves/ jhallar butta making (labour cost only)	r m	2602 68	r ft	793 50
Item - 138	20/22 /26 gauge 15" brass sheet Kunpa making and fixing on roof (avg wt 2 kg)	no	7072 50	no	7072 50
Item - 139	20/22 /26 gauge 12" brass sheet Kunpa making and fixing on roof (avg wt 1 8 kg)	no	4778 25	no	4778 25
Item - 140	20/22 /26 gauge 15" copper sheet Kunpa making and fixing on roof (avg wt 2 kg)	no	6866 65	no	6866 65
Item - 141	20/22 /26 gauge 12" copper sheet Kunpa making and fixing on roof (avg wt 1 8 kg)	no	5188 11	no	5188 11
Item - 142	Slate laying on roof	m2	3615 91	ft2	336 05

(ट) खट बाँधने सम्बन्धी कार्य

Item - 143	Single bamboo Scaffolding works	m2	140 67	ft2	13 07
Item - 144	Single Scaffolding using existing Bamboo	m2	96 51	ft2	8 97
Item - 145	Double bamboo Scaffolding works	m2	262 09	ft2	24 36
Item - 146	Single MS black pipe Scaffolding works	m2	294 60	ft2	27 38
Item - 147	Double MS black pipe Scaffolding works	m2	563 61	ft2	52 38

(ड) धातु सम्बन्धी कार्य

Prepared By



Checked By -



Approved By -



Item - 148	Iron belt for Eaves Board	no	193 88	no	193 88
Item - 149	Wind Bell 4" with complete set	no	1006 25	no	1006 25
Item - 150	Making and fixing of Bhairab of 20 gauge Brass plate medium size 4" (avg 255gm weight)	no	1582 00	no	1582 00
Item - 151	20 gauge Copper plate making and fixing on roof	m2	17523 04	ft2	1628 54
Item - 152	Making and fixing of Bhairab of 20 gauge Copper plate medium size 4" (avg 300gm weight)	no	1754 33	no	1754 33
Item - 153	Gold gilding work (new coat) 1/4 tola per sq ft	m2	661024 77	ft2	61433 53


(द) कर्निस सम्बन्धी कार्य

Item - 154	Cornice works in lime, surkhi and sand mortar 1: 1:1 ratio	m2	3933 02	ft2	365 52
------------	--	----	---------	-----	--------



Prepared By - 

Checked By -

Approved By - 
21/10/20